# ENVIRONMENTAL REPORT GROUND AND SURFACE WATER REPORT ADDENDUM 1

for

BARITE HILL MINE
McCormick, South Carolina

Prepared for

GWALIA (USA) LTD. Denver, Colorado

Prepared by

ENVIRONMENTAL TECHNOLOGY ENGINEERING, INC.

August 1989

#### INTRODUCTION

Gwalia (USA) Ltd. has submitted applications to the South Carolina Land Resources Conservation Commission (LRC) and Department of Health and Environmental Control (DHEC) to allow the construction and operation of gold mining activities and waste handling facilities at the Barite Hill Mine site in McCormick County, South Carolina. The proposed mine site is located on approximately 1,600 acres, two miles south of the Town of McCormick along U.S. Highway 221. As part of the application for the LRC permit, environmental studies are being conducted at the site to establish background conditions prior to the initiation of mining activities.

Environmental Technology Engineering, Inc. (ETE) has been contracted to install ground water monitor wells and collect background sampling data from the wells and on-site streams for presentations to the necessary state agencies. This report presents the data gathered for presentation to LRC to meet their permitting requirements.

#### DATA PROCUREMENT

### Ground Water

Between July 8, 1989 and July 19, 1989, ETE installed five (5) monitor wells at the mine site. The five (5) wells are located as indicated on Figure 1. The wells were installed downgradient of the three (3) proposed waste disposal areas. Copies of the boring logs for each well are included in Appendix 1.

Background samples were collected from monitor wells GW-2, GW-3, and GW-6 on August 1, 1989. Sampling parameters were selected based on the effluent limits proposed in the draft NPDES permit plus the appropriate indicator parameters. Field data is presented in Table 1. Copies of the analytical results and the chain-of-custody forms are included in Appendix 2.

#### Surface Water

Surface water and sediment samples were collected on July 20, 1989 from the tributaries of Hawe Creek located on the site. Samples were taken at the approximate locations of Outfalls 001, 002 and 003 as shown on Figure 1. Sampling parameters were selected based on the effluent limits proposed in the draft NPDES permit plus the appropriate indicator parameters. Field data is presented in Table 1. Copies of the analytical results and chain-of-custody forms are included in Appendix 2.

TABLE 1
Barite Hill Gold Mine
Field Data
Background Sampling

GW-2 GW-3 GW-6 Outfall 001 Outfall 002	<u>pH</u> 7.2 6.2 6.6 6.5 6.8 6.9	spec. <u>Cond.</u> 550 200 650	Water Level T.O.C.  13.6 ft. 8.3 ft. 19.9 ft.
Outfall 003			

# SUMMARY

A review of the analytical data for the ground water and stream, sediment and water, background samples indicates that levels are within the range of values native to South Carolina and will provide a good data base for comparison of future data collected from the site.




FIGURE 1 SITE LAYOUT MAP SOURCE: D.P. ENGINEERING



		7			7	ENVIRON CON	IMENTAL SULTING I					NC.	TEST BORING LOG
								PROGEOLO					BORING NO. FIFE - GW 1
PROJE						Well Ins				SHEET NO. I OF 1			
CLIENT		Gwa	بلن	<u>a US</u>	<u>SA =</u>	<u> Barite</u>	<u> Hill P</u>	roject	McC	ormick	JOB NO. 262-88101		
GROUN				I UK:	<u>F</u>	PE		<del>1</del>	CAS.	CAMP	10005	TUDE	ELEVATION DATE SHARTED 7/13/89
DATE	TIN			ATE	R EL.	SCF	REEN	TYPE	CAS.	SAMP.	COHE	IUBE	DATE FINISHED 7/17/89
	<del>                                     </del>											DRILLER J. Leaphart	
								WT.					INSPECTOR E. Aufderhaar
	L							FALL					P. Lorris
CONST	ELL RUCTI	ION	SEPTH THE					,	CLASSII	FICATIO	N		REMARKS
7.HOL	4.PVC CASING	0 SLOTTED	5		STRAIGHT AUGER		Tan, CLAY  Tan, CLAY  CLAY	white white with 1 horizo	weathe weathe imited ns	red <u>SA</u> red <u>SA</u> argil	PROLIT	FIC	Moist Moist
GRAVEL		CSCREEN .	20				CLAY		<del></del>	red <u>SA</u>			Moist Becoming Saturated Saturated TD Boring = 23.0'
1 L					i		CLAY	WITT CE	weaute	teu <u>sa</u>	PROLIT.	LIC	TD Well Set = 21.0'
800	ING												
			- 25				1						]
T.D.	,-23						1						ļ
			. !				1						
													}
i			┝				1						1
*			30				Į						
			<b> </b>				}						ļ
I			<b>†</b>				1						·
1			ľ	[			ł						
			[	[ ]			ļ						
1			-35				}						
1			[										
				1			}						
ŧ							]						
J			40				<b> </b>						
			١. ٠										. [
j			<b> </b>				}						
1			ŀ	<b>l</b> i		<u> </u>							
			ŀ			<b> </b>							
			45			ļ							у -
1			ŀ			<b> </b> -	1						·

			3				E			TECHNO				NC,	TEST BORING LOG
	_			_	=	1.			HYC	ROGEOLO	GIC SERV	/ICES			BORING NO. ETE - GW 2
PROJE				Gro	undw	ate	r V	Well I	nstalla	ation					SHEET NO. I OF 1
CLIEN.									ite Hi	ll Pro	ect -	McCom	nick,	s.c.	JOB NO. 262-88101
BORIN					TOR:		<u> </u>	<u> </u>					· .		ELEVATION
GROU					<del></del>	<del></del>					CAS.	SAMP.	CORE	TUBE	DATE SHARTED 7/14/89
DATE	+	. TI	ME	<u> </u>	ATE	R EL	$\dashv$	SCH	EEN	TYPE					DATE FINISHED 7/19/89
	╁						-		<del></del>	DIA. WT.	<u> </u>				DRILLER J. Leaphart INSPECTOR P. Lorris
	╁			├						FALL					E. Aufderhaar
				<del>'                                    </del>	ì			LE				L	1		F. Autgernaar
CONST	/E	LL UCI	rion	DEPTH	NO.			OWS PER		(	CLASSIF	ICATIO	<b>V</b>		REMARKS
GROUT				5					and (						
GR(		CASING		<u>}</u>					Tan, and (	yellow LAY	SAND	(f.m.c	:.), <u>s</u>	<u>шт,</u>	
	(	ا بد		İ.,		l	Г								Moist
ဇ	9	} د	7	10		Œ						<i></i>			POISC
PLUG		[ ]	1	[		AUGER				yellow				,	
٩H	5	• ]	1			Ž			(I.m.	.c.), §	TITI an	o CLAY	<u>-</u>	j	į
- 11		- }	1		•				i						<b>.</b>
) [		j	1	-15		표	L								
7.HOLE		l	SLOTTED			STRAIGHT			Tan.	white,	dense	BARTT	TE wit	h	
되ト	_		15			<b>H</b>			weath	nered z	ones	- 11111	= "	••	
~  N		//	19			တ	L		waaa	.c.cu z	OTICO				٠.
- 1 17		/1		L		l									
- 11	1	/	15	20		l	L							i	Moist
RAVEL	١	/	5	: [		ĺ	<u> </u>		170	donco	+	<u></u>			
<b>≩</b>	1		Z			1	<u> </u>			dense, E with				erea l	
띪	1	۱ ۱	l m			ĺ							us		
11	/	N	SCR			l	<b> </b>		UNIO	SITE oc	CULLII	9			
- 1.1/	Ι,	71		25			<u> </u>								
1.1		7	Ψ	-		ĺ	<u> </u>		Dense	e, tan,	brown	weath	ered		Saturated
			_	}		l	}—		BARIT						
				-			-								
				-			-								
				30			┝								
				ŀ	1	i	-								!
				ł		ł	$\vdash$	<del></del> {							
				ŀ		İ	├─								
				ł	1		┝								
				-35		l	$\vdash$								
				ŀ		1	$\vdash$								
				t		1	H								
				t			1								
				<b>†</b>	•		一								
				40		1	一								
•				t	(	l	$\vdash$								
				t	{	l	Г								
				t		ĺ	Г								
				1	[	i									
				[45	1	l									ÿ ÷

E		É			ENVIRON	SULTING E		S AND HY	DROGEOL		NC.	TEST BORING LOG
PROJE	CT: C	<b>*</b>	200		Well Ir							BORING NO. ETTE - GW 3
CLIENT					<u>werr in</u> - Barite			+ Ma	Cormic	JOB NO. 262-88101		
BORING	CONTR	ACT	OR:	E.	TE	<u>:                                    </u>	broder:		СОДШЕ	لمصبهما	·	ELEVATION
GROUN	ID WATE	R						CAS.	SAMP.	CORE	TUBE	DATE SHARTED 7/8/89
DATE	. TIME	W	ATE	R EL.	SCR	EEN	TYPE					DATE FINISHED 7/11/89
<b></b>							DIA.					DRILLER J. Leaphart
<b></b>							WT.					INSPECTOR P. Lorris
<b> </b>	لــــــا	r 1	<u> </u>		MDI E	·	FALL	L				
	ELL RUCTION	DEPTH FEET	SAMPLE NO. TYPE BLOWS PER				(	CLASSIF	ICATIO	N		REMARKS
<i>m</i> d	4.PVC CASING	0 6		Auger		SILT	e brow & CLAY		<del></del>		E.	
7.HOLE	.010	-10		STRAIGHT A			, SILT	Y CLAY	trace	(+)	E.	
GRAVEL 7	SCREENE:010	-15		STR		ARGIL	dense LITE s	lightl	y weat	Moist		
$\ \cdot\ $	<b>\</b>	-					dense LITE,			nes		Fractures saturated
		20										
: 1		-25										
:												
1		30										
1		-35									!	
}		40									:	
1		-45										Ÿ

					ENVIRON CON	TECHNO INGINEER	S AND HY	DROGEOL		NC.	TEST BORING LOG BORING NO. <sub>ETE - GW 5</sub>	
PROJE	CT:	Gro	ound	wate	Well I	nstalla	ation			SHEET NO. I OF 1		
CLIENT		Cw	alia	TISA	- Barit			± Mc	Comic	JOB NO. 262-88101		
BORIN	G CONT	TRAC	TOR	FI	?					_ •		ELEVATION
	ND WAT	ER	1/A T	R EL.	L.   SCREEN		TYPE	CAS.	SAMP.	CORE	TUBE	DATE SHARTED 7/11/89
DATE	TIME		WAIR	H EL	L. SCHEEN		DIA.				<del></del>	DATE FINISHED 7/13/89 DRILLER J. Leaphart
<b>—</b>	┼	+-			_ <del> </del>		WT.					INSPECTOR P. Lorris
	1						FALL					E. Aufderhaar
		Ī.	ī	SA	MPLE							
	VELL RUCTION	ZOEPTI	ио	. TYPE	BLOWS PER 6 INCHES		(	CLASSIF	ICATIO	<b>N</b>		REMARKS
аноит						f/m/c	orange trace weathe	e (-) n	nica			
BnJd		- - - - -		AUGER		<u>_</u>	dense,			Moist		
HOLE	VC CASING	2		STRAIGHT A			dense,	<del></del>	<del> </del>			· · ·
	10 4.PVC	2	3									
GRAVEL	SCHEET 010	3/					dense,					Fractures
						Very	dense,	tan 8	white	BARI	TE	Saturated @ 30'
 		-2										
} -! 		4	5									у

Ē				Ê			E		IMENTAL SULTING E		S AND HY	DROGEOL		NC.	TEST BORING LOG BORING NO. <sub>ETE - GW 6</sub>
PROJ	EC	T:		Gra	Ound	-lwate	ər	Well	Instal			<del></del>	SHEET NO. I OF 1		
CLIEN	IT:			Gwa	alia	a US	A -	- Bari	te Hil	l Proje	ect - I	McCorm	ick, S	s.c.	JOB NO. 262-88101
BORIN				RACT	ror:	ET	E						•		ELEVATION
GROU						=-=-					CAS.	SAMP.	CORE	TUBE	DATE SHARTED 7/12/89
DATE	4	TI	ME	w	ATE	R EL.		SCF	EEN	TYPE					DATE FINISHED 7/18/89
<b></b>	+			<del> </del>			-			DIA. WT.				<b> </b>	DRILLER J Teaphart
<b>}</b>	+			<del>                                     </del>			$\dashv$			FALL					E. Aufderhaar
				T	ī	SA	MP	LE	<u> </u>		<u> </u>	·			D. Autucrimut
соиз	WE TR		LION	PEETH	NO.	$\overline{}$	_	OWS PER INCHES		(	CLASSIF	CATIO	N		REMARKS
GRAVEL plug 7"HOLE GROUT		CASING		10 10 15 20 28		STRAIGHT AUGER		INCHES	Red Control Red Co	dense, weath	red BAI d DE bluewith in Barite	green nterst:	itial		Moist Withstood up to 700 PSI Water Marks  Saturated @ 22' with fractures evident
<u> </u>				- - -45											y ·

APPENDIX 2



Sampling, testing, mobile labs

#### ANALYTICAL SUMMARY

BARITE HILL PROJECT McCORMICK, SOUTH CAROLINA JULY 1989

PRESENTED TO

MR. MICHAEL YOUNG

OF

ENVIRONMENTAL TECHNOLOGY ENGINEERING, INC.

August 22, 1989

Wadsworth/ALERT Laboratories, Inc.

Michael P. Sekel.

Laboratory Manager



# INTRODUCTION

This report summarizes the analytical results of water and soil samples from the Barite Hill project in McCormick, South Carolina. The samples were submitted by Environmental Technology Engineering, Inc. to Wadsworth/ALERT Laboratories, Inc. on 21 July and 2 August 1989. Wadsworth/ALERT Laboratories, Inc. provided independent, analytical services for this project as a sub-contractor to Environmental Technology Engineering, Inc. of Lexington, South Carolina under the direction of Mr. Michael Young, Project Manager.

A total of six (6) water samples and three (3) soil samples collected by ETE and submitted to Wadsworth/ALERT Laboratories, Inc. The first set, received on 21 July 1989, had three (3) water samples and three (3) soil samples. second set, received on 2 August 1989, contained six (6) water samples. Three (3) of the samples were resamples of the first set because of holding time constraints. samples were accepted into the laboratory in accordance with documented sample acceptance procedures. All samples were for a variety of inorganic and heavy metal analyzed parameters as specified by ETE. These parameters associated analytical methods are outlined in this report along with a summary description of Wadsworth/ALERT Laboratories, Inc. QA/QC program. Sample analytical results are sequentially presented at the rear of the report.



#### ANALYTICAL METHODS

Wadsworth/ALERT Laboratories utilizes only USEPA approved analytical methods and instrumentation. The analytical methods utilized for the analysis of these samples are listed below.

PARAMETER	METHOD
-----------	--------

#### ORGANICS

Oil & Grease	** SW846 Method 9070,9071
Phenolics	** SW846 Method 9066
Total Organic Carbon	** SW846 Method 9060

#### **METALS**

Arsenic	EPA Method 206.2	** SW846 Method 7060
Barium	EPA Method 208.1	** SW846 Method 7080
Cadmium	EPA Method 213.1	** SW846 Method 7130
Chromium	EPA Method 218.1	** SW846 Method 7190
Chromium+6	EPA Method 218.5	** SW846 Method 7196
Copper	EPA Method 220.1	** SW846 Method 7210
Lead	EPA Method 239.1	** SW846 Method 7420
Mercury	EPA Method 249.1	** SW346 Method 7520
Selenium	EPA Method 272.1	** SW846 Method 7760
Zinc	EPA Method 289.1	** SW846 Method 7950

# INORGANIC - NON-METALLICS

Cyanide, total	EPA Method 335.2	** SW846 Method 9010
Total Suspended Solids		** EPA Method 160.2

Note: \*\* indicates usage of this method to obtain results for this report.

Note: EPA Methods - Methods for Chemical Analysis of Water and Wastes, USEPA, 600/4-79-020, March, 1983. July, 1982.

Std.Methods - Standard Methods for the Examination of Water and Wastewater, APHA, 16th edition, 1985.

USEPA Methods- from 40CFR Part 136, published in Federal Register on October 26, 1984.

SW846 - Test Methods for Evaluating Solid Waste Physical/Chemical Methods, 3<sup>rd</sup> Edition, USEPA, 1986



# ANALYTICAL RESULTS

The analytical results for the samples submitted by ETE from the Barite Hill project are presented on the following pages.

```
Outfall #1 (water)
Outfall #1 (soil)
Outfall #2 (water)
Outfall #2 (soil)
Outfall #3 (water)
Outfall #3 (soil)
MW-2
MW-3
MW-6
```

MATRIX: <u>Water</u>

LAB #: <u>9G212-1</u>

SAMPLE ID: Outfall #1

analyte	RESULT	DET.LIMIT	METHOD	DATE PREP/A	NALYZED
		METALS			
Arsenic	None Detected	10. ug/L	SW846 7060	8/07/89	8/08/89
Barium	None Detected	1,000. ug/L	SW846 7080	8/07/89	8/10/89
Cadmium	None Detected	10. ug/L	SW846 7130	8/07/89	8/10/89
Chromium	None Detected	50. ug/L	SW846 7190	8/07/89	8/10/89
Chromium+6	None Detected	50. ug/L	SW846 7196	8/07/89	8/11/89
Copper	None Detected	200. ug/L	SW846 7210	8/07/89	8/10/89
Lead	None Detected	50. ug/L	SW846 7420	8/07/89	8/10/89
Mercury	None Detected	2. ug/L	SW846 7520	8/07/89	8/16/89
Selenium	None Detected	10. ug/L	SW846 7760	8/07/89	8/08/89
Zinc	None Detected	50. ug/L	SW846 7950	8/07/89	8/08/89
	WET	CHEMISTRIES		<b>%</b> •	
Cyanide, total	None Detected	.005 mg/L	SW846 9010	7/28/89	7/28/89
Oil & Grease	None Detected	1.0 mg/L	SW846 9070,9	0,71 7/25/89	7/25/89
Phenolics, total	None Detected	.01 mg/L	SW846 9066	7/27/89	7/28/89
Total Suspended Solids	16. mg/L	1. mg/L	EPA 160.2	7/27/89	7/27/89

LAB #: <u>9G212-1A</u>

SAMPLE ID: Outfall #1 MATRIX: Soil

ANALYTE	RESULT	DET.	LIMIT	METI	HOD DA	TE PREP/A	NALYZED
	:	<u>METALS</u>				· · · · · · · · · · · · · · · · · · ·	
Arsenic	1.9 mg/kg	0.8	mg/kg	SW846		7/31/89	8/14/89
Barium	28. mg/kg	20.	mg/kg	SW846	7080	7/31/89	8/10/89
Cadmium	1.5 mg/kg	1.0	mg/kg	SW846	7130	7/31/89	8/10/89
Chromium	82. mg/kg	4.0	mg/kg	SW846	7190	7/31/89	8/10/89
Chromium+6	None Detected	4.0	mg/kg	SW846	7196	7/31/89	7/27/89
Copper	76. mg/kg	8.0	mg/kg	SW846	7210	7/31/89	8/10/89
Lead	22. mg/kg	10.	mg/kg	SW846	7420	7/31/89	8/10/89
Mercury	None Detected	0.040	mg/kg	SW846	7520	7/31/89	8/08/89
Selenium	None Detected	0.1	mg/kg	SW846	7760	7/31/89	8/08/89
Zinc	69. mg/kg	5.0	mg/kg	SW846	7950	7/31/89	8/08/89
	WET	CHEMISTRIE	<u>s</u>				
Cyanide, total	None Detected	.5	mg/kg	SW846	9010	7/28/89	7/28/89
Oil & Grease	None Detected	1.0	mg/kg	SW846	9070,9071	7/26/89	7/26/89
Phenolics, total	None Detected	.2	mg/kg	SW846	9066	7/27/89	7/28/89

MATRIX: Water

LAB #: 9G212-2

SAMPLE ID: Outfall #2

ANALYTE	RESULT DET.LIMIT METHOD			DATE PREP/ANALYZED		
		METALS				
Arsenic Barium	None Detected None Detected	10. ug/L 1,000. ug/L	SW846'7060 SW846 7080	8/07/89 8/08/89 8/07/89 8/10/89		
Cadmium Chromium	None Detected None Detected	10. ug/L 50. ug/L	SW846 7130 SW846 7190	8/07/89 8/10/89 8/07/89 8/10/89		
Chromium+6 Copper	None Detected None Detected	50. ug/L 200. ug/L	SW846 7196 SW846 7210	8/07/89 8/11/89 8/07/89 8/10/89		
Lead Mercury	None Detected None Detected	50. ug/L 2. ug/L	SW846 7420 SW846 7520	8/07/89 8/10/89 8/07/89 8/16/89		
Selenium Zinc	None Detected None Detected	10. ug/L 50. ug/L	SW846 7760 SW846 7950	8/07/89 8/08/89 8/07/89 8/08/89		
	WET	CHEMISTRIES				
Cyanide, total	None Detected	.005 mg/L	SW846 9010	7/28/89 7/28/89		
Oil & Grease	None Detected	1.0 mg/L	SW846 9070,907	71 7/25/89 7/25/89		
Phenolics, total	None Detected	.01 mg/L	SW846 9066	7/27/89 7/28/89		
Total Suspended Solids	3. mg/L	1. mg/L	EPA 160.2	7/27/89 7/27/89		

SAMPLE ID: Outfall #2 MATRIX: Soil

ANALYTE	RESULT DET.LIMIT METHOD				HOD D	DATE PREP/ANALYZED		
		METALS					·	
Arsenic Barium	3.7 mg/kg 56. mg/kg	2.0 20.	mg/kg mg/kg	SW846 SW846		7/31/89 7/31/89	8/14/89 8/10/89	
Cadmium Chromium	1.7 mg/kg 71. mg/kg	1.0 4.0	mg/kg mg/kg	SW846 SW846		7/31/89 7/31/89	8/10/89 8/10/89	
Chromium+6 Copper	None Detected 10. mg/kg	4.0 4.0	mg/kg mg/kg	SW846 SW846		7/31/89 7/31/89	7/27/89 8/10/89	
Lead Mercury	14. mg/kg None Detected	10. 0.040	mg/kg mg/kg	SW846 SW846		7/31/89 7/31/89	8/10/89 8/08/89	
Selenium Zinc	None Detected 23. mg/kg	0.1 1.0	mg/kg mg/kg	SW846 SW846		7/31/89 7/31/89	8/08/89 8/08/89	
	WET	CHEMISTRIE:	<u>3</u>					
Cyanide, total	None Detected	• 5	mg/kg	SW846	9010	7/28/89	7/28/89	
Oil & Grease	None Detected	1.0	mg/kg	SW846	9070,907	7/26/89	7/26/89	
Phenolics, total	.3 mg/kg	.2	mg/kg	SW846	9066	7/27/89	7/28/89	

LAB #: 9G212-2A

SAMPLE ID: Outfall #3 MATRIX: Water

LAB #:

9G212-3

ANALYTE	RESULT .	RESULT DET.LIMIT METHOD		DATE PREP/ANALYZED		
		<u>METALS</u>				
Arsenic Barium	None Detected None Detected	10. ug/L 1,000. ug/L	SW846 7060 SW846 7080	8/07/89 8/08/89 8/07/89 8/10/89		
Cadmium Chromium	None Detected None Detected	10. ug/L 50. ug/L	SW846 7130 SW846 7190	8/07/89 8/10/89 8/07/89 8/10/89		
Chromium+6 Copper	None Detected None Detected	50. ug/L 200. ug/L	SW846 7196 SW846 7210	8/07/89 8/11/89 8/07/89 8/10/89		
Lead Mercury	None Detected None Detected	50. ug/L 2. ug/L	SW846 7420 SW846 7520	8/07/89 8/10/89 8/07/89 8/16/89		
Selenium Zinc	None Detected None Detected	10. ug/L 50. ug/L	SW846 7760 SW846 7950	8/07/89 8/08/89 8/07/89 8/08/89		
	WET	CHEMISTRIES	·	,		
Cyanide, total	None Detected	.005 mg/L	SW846 9010	7/28/89 7/28/89		
Oil & Grease	None Detected	1.0 mg/L	SW846 9070,9	0071 7/25/89 7/25/89		
Phenolics, total	None Detected	.01 mg/L	SW846 9066	7/27/89 7/28/89		
Total Suspended Solids	66. mg/L	1. mg/L	EPA 160.2	7/27/89 7/27/89		

LAB #: <u>9G212-3A</u>

SAMPLE ID: Outfall #3

MATRIX: Soil

ANALYTE	RESULT DET.LIMIT METHOD		iod di	DATE PREP/ANALYZED			
		<u>METALS</u>					
Arsenic	11.9 mg/kg	2.0	mg/kg	SW846	7060	7/31/89	8/14/89
Barium	181. mg/kg	20.	mg/kg	SW846	7080	7/31/89	8/10/89
Cadmium	1.2 mg/kg	1.0	mg/kg	SW846	7130	7/31/89	8/10/89
Chromium	50. mg/kg	4.0	mg/kg	SW846	7190	7/31/89	8/10/89
Chromium+6	None Detected	4.0	mg/kg	SW846	7196	7/31/89	7/27/89
Copper	31. mg/kg	4.0	mg/kg	SW846	7210	7/31/89	8/10/89
Lead	30. mg/kg	10.	mg/kg	SW846	7420	7/31/89	8/10/89
Mercury	None Detected		mg/kg	SW846	7520	7/31/89	8/08/89
Selenium	None Detected	0.1	mg/kg	SW846	7760	7/31/89	8/08/89
Zinc	63. mg/kg	5.0	mg/kg	SW846	7950	7/31/89	8/08/89
	WET	CHEMISTRIE:	<u> </u>				
Cyanide, total	None Detected	.5	mg/kg	SW846	9010	7/28/89	7/28/89
Oil & Grease	None Detected	1.0	mg/kg	SW846	9070,907	7/26/89	7/26/89
Phenolics, total	None Detectied	.2	mg/kg	SW846	9066	7/27/89	7/28/89

.

MATRIX: Water

LAB #: 9H021-1

SAMPLE ID: MW-2

ANALYTE	RESULT	DET.LIMIT	METHOD	DATE PREP/ANALYZED
		METALS		
Arsenic	None Detected	10. ug/L	SW846 7060	8/07/89 8/22/89
Barium	None Detected	1,000. ug/L	SW846 7080	8/07/89 8/10/89
Cadmium	None Detected	10. ug/L	SW846 7130	8/07/89 8/10/89
Chromium	None Detected	50. ug/L	SW846 7190	8/07/89 8/10/89
Chromium+6	None Detected	50. ug/L	SW846 7196	8/07/89 8/22/89
Copper	None Detected	200. ug/L	SW846 7210	8/07/89 8/10/89
Lead	None Detected	50. ug/L	SW846 7420	8/07/89 8/09/89
Mercury	None Detected	2. ug/L	SW846 7520	8/07/89 8/16/89
Selenium	None Detected	10. ug/L	SW846 7760	8/07/89 8/08/89
Zinc	110. ug/L	50. ug/L	SW846 7950	8/07/89 8/08/89
	WET	CHEMISTRIES		
Cyanide, total	None Detected	.005 mg/L	SW846 9010	8/04/89 8/04/89
Phenolics, total	None Detected	.01 mg/L	SW846 9066	8/09/89 8/10/89
Total Organic Carbon	2. mg/L	1. mg/L	SW846 9060	8/11/89 8/11/89

SAMPLE ID: MW-3 MATRIX: Water

LAB #: 9H021-2

ANALYTE	RESULT DET.LIMIT METHOD		DATE PREP/ANALYZED	
		METALS		
Arsenic Barium	None Detected None Detected	10. ug/L 1,000. ug/L	SW846 7060 SW846 7080	8/07/89 8/14/89 8/07/89 8/10/89
Cadmium Chromium	None Detected None Detected	10. ug/L 50. ug/L	SW846 7130 SW846 7190	8/07/89 8/10/89 8/07/89 8/10/89
Chromium+6 Copper	None Detected None Detected	50. ug/L 200. ug/L	SW846 7196 SW846 7210	8/07/89 8/11/89 8/07/89 8/10/89
Lead Mercury	None Detected None Detected	50. ug/L 2. ug/L	SW846 7420 SW846 7520	8/07/89 8/09/89 8/07/89 8/16/89
Selenium Zinc	None Detected 160. ug/L	10. ug/L 50. ug/L	SW846 7760 SW846 7950	8/07/89 8/08/89 8/07/89 8/08/89
	WET	CHEMISTRIES		•
Cyanide, total	None Detected	.005 mg/L	SW846 9010	8/04/89 8/04/89
Phenolics, total	None Detected	.01 mg/L	SW846 9066	8/09/89 8/10/89
Total Organic Carbon	None Detected	1. mg/L	SW846 9060	8/11/89 8/11/89

SAMPLE ID: MW-6 MATRIX: Water

LAB #:

9H021-3

ANALYTE	RESULT	DET.LIMIT	METHOD	DATE PREP/ANALYZED	
		<u>METALS</u>			
Arsenic Barium	None Detected None Detected	10. ug/L 1,000. ug/L	SW846 7060 SW846 7080	8/07/89 8/08/89 8/07/89 8/10/89	
Cadmium Chromium	None Detected None Detected	10. ug/L 50. ug/L	SW846 7130 SW846 7190	8/07/89 8/10/89 8/07/89 8/10/89	
Chromium+6 Copper	None Detected None Detected	50. ug/L 200. ug/L	SW846 7196 SW846 7210	8/07/89 8/11/89 8/07/89 8/10/89	
Lead Mercury	None Detected None Detected	50. ug/L 2. ug/L	SW846 7420 SW846 7520	8/07/89 8/09/89 8/07/89 8/16/89	
Selenium Zinc	None Detected None Detected	10. ug/L 50. ug/L	SW846 7760 SW846 7950	8/07/89 8/08/89 8/07/89 8/08/89	
	WET	<u>CHEMISTRIES</u>		•	
Cyanide, total	None Detected	.005 mg/L	SW846 9010	8/04/89 8/04/89	
Phenolics, total	None Detected	.01 mg/L	SW846 9066	8/09/89 8/10/89	
Total Organic Carbon	4. mg/L	1. mg/L	SW846 9060	8/11/89 8/11/89	

LAB #: 9G212

SAMPLE ID: <u>Lab Blank</u> MATRIX: <u>Water</u>

ANALYTE	RESULT	DET.LIMIT	METHOD	DATE PREP/ANALYZED
		<u>METALS</u>		
Arsenic Barium	None Detected None Detected	10. ug/L 1,000. ug/L	SW846 7060 SW846 7080	8/07/89 8/08/89 8/07/89 8/10/89
Cadmium Chromium	None Detected None Detected	10. ug/L 50. ug/L	SW846 7130 SW846 7190	8/07/89 8/10/89 8/07/89 8/10/89
Chromium+6 Copper	None Detected None Detected	50. ug/L 200. ug/L	SW846 7196 SW846 7210	8/07/89 8/11/89 8/07/89 8/10/89
Lead Mercury	None Detected None Detected	50. ug/L 2. ug/L	SW846 7420 SW846 7520	8/07/89 8/10/89 8/07/89 8/16/89
Selenium Zinc	None Detected None Detected	10. ug/L 50. ug/L	SW846 7760 SW846 7950	8/07/89 8/08/89 8/07/89 8/08/89
	WET	CHEMISTRIES		
Cyanide, total	None Detected	.005 mg/L	SW846 9010	7/28/89 7/28/89
Oil & Grease	None Detected	1.0 mg/L	SW846 9070,9	071 7/25/89 7/25/89
Phenolics, total	None Detected	.01 mg/L	SW846 9066	7/27/89 7/28/89
Total Suspended Solids	None Detected	1. mg/L	EPA 160.2	7/27/89 7/27/89

SAMPLE ID: Lab Blank MATRIX: Solid

LAB #:

9G212

ANALYTE	RESULT	DET.LIMIT	METHOD	DATE PREP/ANALYZED	
		<u>METALS</u>			
Arsenic	None Detected	0.01 mg/L	SW846 7060	7/31/89	8/08/89
Barium	None Detected	$1.0  ext{ mg/L}$	SW846 7080	7/31/89	8/10/89
Cadmium	None Detected	0.05 mg/L	SW846 7130	7/31/89	8/10/89
Chromium	None Detected	0.2 mg/L	SW846 7190	7/31/89	8/10/89
Chromium+6	None Detected	0.2 mg/L	SW846 7196	7/31/89	7/27/89
Copper	None Detected	0.2 mg/L	SW846 7210	7/31/89	8/10/89
Lead	None Detected	0.2 mg/L	SW846 7420	7/31/89	8/10/89
Mercury	None Detected	0.002 mg/L	SW846 7520	7/31/89	8/08/89
Selenium	None Detected	0.01 mg/L	SW846 7760	7/31/89	8/08/89
Zinc	None Detected	0.05 mg/L	SW846 7950	7/31/89	8/08/89
	WET	CHEMISTRIES			
Cyanide, total	None Detected	.005 mg/L	SW846 9010	7/28/89	7/28/89
Oil & Grease	None Detected	1.0 mg/kg	SW846 9070,9	071 7/26/89	7/26/89
Phenolics, total	None Detected	0.01 mg/L	SW846 9066	7/28/89	7/28/89

LAB #: 9H021

SAMPLE ID: <u>Lab Blank</u>

MATRIX: <u>Water</u>

i i

ANALYTE	RESULT DET.LIMIT METHOD		DATE PREP/ANALYZED		
		<u>METALS</u>			•
Arsenic	None Detected	10. ug/L	SW846 7060	8/07/89	8/08/89
Barium	None Detected	1,000. ug/L	SW846 7080	8/07/89	8/10/89
Cadmium	None Detected	10. ug/L	SW846 7130	8/07/89	8/10/89
Chromium	None Detected	50. ug/L	SW846 7190	8/07/89	8/10/89
Chromium+6	None Detected	50. ug/L	SW846 7196	8/07/89	8/11/89
Copper	None Detected	200. ug/L	SW846 7210	8/07/89	8/10/89
Lead	None Detected	50. ug/L	SW846 7420	8/07/89	8/09/89
Mercury	None Detected	2. ug/L	SW846 7520	8/07/89	8/16/89
Selenium	None Detected	10. ug/L	SW846 7760	8/07/89	8/08/89
Zinc	None Detected	50. ug/L	SW846 7950	8/07/89	8/08/89
	WET	CHEMISTRIES			
Cyanide, total	None Detected	.005 mg/L	SW846 9010	7/27/89	7/27/89
Phenolics, total	None Detected	.01 mg/L	SW846 9066	7/27/89	7/28/89
Total Organic Carbon	None Detected	1. mg/L	SW846 9060	7/27/89	7/27/89

WADSWORTH/ALERT LABORATORIES 4101 SHUFFEL DRIVE N.W./NORTH CANTON, OHIO 4,4720 15821 (216) 497-9396 507 Chain-of Custody Record PROJECT NAME/LOCATION PROJ. NO. PARAMETER). 262 88101 M'CORMICK SK SAMPLERS: (Signature) ETE CON-TAINERS LEAPHART . REMARKS GRAB. DATE TIME STATION LOCATION STA. NO. 7/20/000 96212-OUTFALL # SAMPLES # 2 7/201/30 # 3 11 50IL DOT FALL 1000 #1 SOIL SAMPLED FOR METALS Gala-an) PhenoLS CYANIDE + OIL + GRET ろいてし 1330 SOIL Relinquished by: (Signature) Relinquished by: (Signature) 7/34/817-75-89 Received by: (Signature) Date / Time Received by: (Signature) Date / Time 1700 /26 Received by: (Signature) Relinquished by: (Signature) Relinquished by: (Signature) Date / Time Date / Time Date / Time Received for Laboratory by: Date / Time Remarks Relinquished by: (Signature) (Signature)

Distribution Original Accompanies Shipment. Copy returned with Report.

# **WADSWORTH/ALERT LABORATORIES**

4101 SHUFFEL DRIVE N.W./NORTH CANTON, OHIO 44720 (216) 497-9396

Chain-of Custody Record

FUA

Nº 15.

BARITE HILL SIC NO. SAMPLERS: (Signature) OF HOOK CON-**REMARKS TAINERS** SOMP TIME STA. NO. DATE STATION LOCATION 5 MW2 1320 d STREAM OUT FALL 3 /320 -11 1 Relinquished by: (Signature) 9/5/07 Relinquished by: (Signature) Received by: (Signature) 8/2/89 Date / Time Date / Time Received by: (Signature) 0900 Relinquished by: (Signature) Date / Time Received by: (Signature) Relinquished .py: (Signature) Date / Time Received by: (Signature) \*\* : AND SHIPPED TO LAR Date / Time Received for Laboratory by: Relinquished by: (Signature) Date / Time (Signature) Distribution Original Accompanies Shipment. Copy returned with Report.